250. A non-watertight lined excavation in the ground that receives the discharge of a sanitary drainage system or part thereof, designed to retain the organic matter and solids discharging therefrom, but permitting the liquid to seep through the bottom and sides of the cesspool.

(a) Chase

(c) Privy

(b) Cesspool

(d) Receptor

251. What plans are useful in planning the installation of sewers, water services, building drains, and hose bibs?

(a) Site plans

(c) Contour plans

(b) Floor plans

(d) Cross-section plans