

214. Which of the following is an acceptable procedure when installing piping in a load-bearing wooden partition?

- (a) Do not drill or notch the studs
- (b) Drill a hole at the sides of the studs
- (c) Make a notch not more than one-half the thickness
- (d) Drill hole through the center of the studs



215. What is the temperature in deg C of 2 liters of water at 30 deg C after 500 calories of heat have been added?

(a) 157 deg C

(c) 175 deg K

(b) 280 deg K

(d) 280 deg C

