300. A septic tank should be at least _____ meters away from any source of water supply wells

(a) 20

(c) 15

(b) 10

(d) 25

- 301. Soil pipe is part of the drainage system, which conveys wastewater containing organic waste, whereas waste pipe is a part that conveys waste containing.
 - (a) Acid
 - (b) Salt
 - (c) Other elements soluble in water
 - (d) All of these