575. Total value of DFU for an installation with the following fixtures: 20 WC (public), 8 UR (pedestal), 2 sink service 2 wash basin (in set), 4 FD

(a) 168 DFU

(c) 174 DFU

(b) 186 DFU

(d) 180 DFU

576. In the water test of the entire plumbing system, all openings should be tightly closed except at

(a) Producing cleanouts

(c) Stack vent

(b) Highest opening

(d) Bleeders