275. Size of building drain for fixtures listed in item no. 70 (see attached tables)

(a) 76 mm

(c) 102 mm

(b) 127 mm

(d) 152 mm

- 276. Except for the plastic piping system, hot and cold water piping may be tested with \_\_\_\_\_
  - (a) 50 psi of the working pressure of the water in the system for at least 15 minutes
  - (b) 100 psi air for at least 10 minutes
  - (c) 35 psi air for at least 15 minutes
  - (d) 40 psi air or 150 psi water for 10 minutes