248. The critical level marking or backflow prevention device or vacuum breaker is a point established by the

(a) Testing laboratory

(c) Inspector

(b) Health officer

(d) Manufacturer

249. What is the fittings installed in the plumbing system to prevent the passage of air, gas, and some vermin through the pipe?

(a) Trap

(c) Flap valve

(b) Check valve

(d) Gate valve